



NOTES:

- 1 - TRENCH AND CONDUIT MUST BE INSPECTED BY VEC PERSONNEL BEFORE FILLING.
- 2 - AFTER CABLE INSTALLATION, TRENCH SHALL BE BACKFILLED AND COMPACTED WITH TAMPING DEVICE TO ACHIEVE MINIMUM 90% COMPACTION.
- 3 - IN CASES WHERE A TRENCH CANNOT BE DUG TO THE REQUIRED DEPTH, THE CONDUIT MAY BE COVERED WITH CEMENT. 4" OF CEMENT WILL EQUAL 12" OF TRENCH. A MINIMUM OF 4" OF CEMENT MUST BE USED.

Item No.	Material	Qty.

BY: CKD

DATE: 11/15/01



SECONDARY TRENCH DETAIL

STANDARD
DETAIL

SK-76